

Right To Play						
Mini Football Playground-Chanay						
Bill of Quantities and detailed specifications						
	Unit	Quantity	Price per unit		Notes	Discreption
	<i>This indicates the unit used for the pricing of the item.</i>	<i>This indicates the quantity of the listed item.</i>	<i>Please specify the price per unit of each one of the listed items.</i>	<i>Total (LBP)</i>	<i>Please add notes. The more detailed the budget is the better. Where possible indicate the break down of the price indicated in the 'price per unit' column.</i>	<i>Please add in this section any information that can provide us details about the quality of products provided (Brand, Material, Certification,performance,resistance, installation...etc)</i>
CHEHOUR rehabilitation Saha2						
<i>This project will mainly consist of 3 works: floor repair (demolition of existing floor + pouring of new concrete floor), metal shading roof repair, concrete seats. The materials used will mainly be concrete and steel.</i>						
PROJECT ACTIVITIES (SUPPLIES/MATERIALS)						
Ground works						
General labour	ppd	21			Demolition of 460 m2 of the existing floor as it is not levelled. Please indicate the price of the labour per day. Specify the number of people you estimate to have on site and how much each worker will be paid.	
Soil backfill	m3	46			After demolishing the existing floor, the ground will be filled up and levelled prior to adequate the new concrete screed.	
Reinforced concrete screed	m3	46			A new concrete pouring, approximately 10cm thick and with an adequate slope to drain the water, will be done to achieve a good levelled finished flooring surface. Price includes materials and labour.	
Total						
Shading roof remedial works						
Concrete footings	m3	0.6			Foundations of the new shading roof columns. Price includes materials and labour.	
Scaffolding	day	4			The scaffolding is needed to support the metal shading roof while the columns are replaced.	
General labour	ppd	4			Installation of the scaffolding and removal of the columns (21) of the existing shading roof. Please indicate the price of the labour per day. Specify the number of people you estimate to have on site and how much each worker will be paid.	
Total						
Metal works					For the steel cost please indicated the price per kg, which includes the cost of materials + waterproof and finished colored coat painting (all inclusive of labour). If you would like to indicate the prices differently please provide with a detailed break down. The welder will be in charge of preparing and installing of the new columns of the shading roof and the basketball hoop.	
Steel bars 3x3cm	n	3				
	kg	37.77			Structure of the wall mounted basketball hoop.	
Steel bars Ø2"	n	21				
	kg	441			New columns for the shading roof.	
Steel flat bars (3mm thick)	n	1				
	kg	4.2			Support frame of the basketball backboard.	
Total						
Concrete works						
CMU blocks	n	376				
Concrete slab and sides	m3	9			The structure of the new concrete benches and planters is made of CMU blocks. The CMU blocks used for the benches are covered by reinforced concrete slab and sides. The concrete finishing must then be polished. Price includes materials and labour.	
Total						

Timber works						
--------------	--	--	--	--	--	--

Plywood board	n	1			Used to make the basketball backboard.	
Total						
Paint works						
Colortek varnish (Urethane)	m2	8			Used to waterproof the basketball backboard. The quantity is calculated assuming a double coat of varnish for each side.	
Colortek road marking paint	m2	300			Used for painting floor games on the concrete flooring and to paint the concrete benches.	
Colortek chalkboard paint (water ba	m2	20			Special paint to create a chalkboard wall by the entrance of the courtyard.	
Skilled labour	ppd	8			Wall and floor painting. Please indicate the price of the labour per day. Specify the number of people you estimate to have on site and how much each worker will be paid.	
Total						
Equipment						
Metal basketball hoop (net included	n	1			It will be purchased ready made.	
Total						
Vegetation						
Plants	n	10			Small-sized plants to be placed into the concrete planters.	
Soil	m3	9			Soil to fill up the concrete planters.	
Skilled gardener	ppd	1			Installation of the plants in the concrete planters. Please indicate the price of the labour per day. Specify the number of people you estimate to have on site and how much each worker will be paid.	
Total						
Fees						
Contractor fee					Note that the fee will also includes all the mixed components (screws, nails, ect.) used during the construction phase.	
Total						
Transports						
Waste removal	n	20				
Total						

Note: Kindly note that detailed drawings of the design will be provided at the selection stage by Right To Play consultant, to be followed by the contractor during the construction phase.

COLLECTIONS	
Ground works	
Shading roof remedial works	
Metal works	
Concrete works	
Timber works	
Paint works	
Equipment	
Vegetation	
Fees	
Transports	
TOTAL AMOUNT	