

BoQ form moving IT/ network equipment in Beirut Office	
Remove IT/ network equipment in Beirut Achrafieh	Install IT/ network equipment in Beirut Adlieh
<p>Location: Beirut, Achrafieh, Sassine Square, Paragon Building Coordinates: 33.88701540827514, 35.52143579615622Map link: https://maps.app.goo.gl/xnSQMHh9BfdCqeLDA</p>	<p>Location: Beirut, Adlieh, Boustany Building, 4th floor Coordinates: 33.88006152606837, 35.518598666705095 Map link: https://maps.app.goo.gl/CYxGxqhhvxtgixdh8</p>
<p>Technical support:</p> <p>The company will be responsible to implement the below tasks to remove all items that belongs to network in Beirut Office.</p> <ol style="list-style-type: none"> 1. Uninstall 7 Ubiquity Access Points in the office. 2. uninstall UPS Eaton with the 15 external batteries and external charger in the server room. 3. Uninstall the server cabinet in the server room, the server cabinet includes: 3 switches 16 and 24 ports, NAS Synology, Firewall Meraki MX85, patch panels, 2 servers, DVR, DSL Modem. 4. Uninstall the projector with stand in the meeting room. 5. Uninstall Central Phone in the office. 	<p>Technical support:</p> <p>The company will be responsible to implement the below tasks to install IT/ network equipment based on the map</p> <ol style="list-style-type: none"> 1. Install/ terminate RJ45 points as showing in the map for all equipment with fluke test after installation, RJ45 sockets have to be CAT6 grade A similar to Leviton. 2. Install and testing Ubiquiti Access points and as showing in the map. 3. Install network cables + cache cables/ cable guide and electrical cables that belong to UPS for the network if needed. The network cables have to be CAT6 grade A similar to Leviton and cache cable have to be with a grade A quality. 4. Install UPS with the batteries in the server room and test it. 5. Readjustment of the cabinet in the server room, testing all the points. 6. Labeling of all the points and send excel table includes all points. 7. The company has to plan that might need to install additional small items during the installation. 8. Install projector with stand in the meeting. 9. Install the Central Phone in the server Room and support with configuration. 10. Install Rj11 points for specific room to have landline phones
<p>DRC prefers to have a site visit by the companies to the Beirut office in the presence of the IT Specialist to have full details about the task.</p>	<p>DRC prefers to have a site visit by the companies to the Beirut office in the presence of the IT Specialist to collect full details about the task and have more information about the distances for the installation.</p>