

Lot 2 - Andkit - North of Lebanon					
DC Hybrid all in one solar LED street lighting systems					
No.	Item Details	Unit	Qty.	Unit Price (USD)	Total Price (USD)
<b>1</b>	<b>Provisional Item</b>				
1.1	Removing, disassembling, transporting, and transferring current lighting fixtures, including old lamps and arms, to the designated authority's storage facility as per the Project Engineer's direction.	UNITS	221	--	--
<b>2</b>	<b>All in one Solar Street Light Fixture</b>				
2.0	Supplying, delivering, installing, testing, commissioning, operating, and finalizing the handover of DC hybrid all-in-one solar LED street light systems, following the scope of work, technical specifications, and provided drawings.	Note			
2.1	LED lighting of at least 50 W , Solar PV modules not less than 70 Wp, lithium iron Phosphate battery not less than ( 40 Ah with 12.8V) with Controller , as per Scope of work and technical specification and drawings.	Set	221	--	--
<b>3</b>	<b>Project sign boards</b>				
3.1	Supplying, installing, and maintaining project signboards (1.6m x 1.4m with 1.2m height from the ground), Material to be advised and approved prior execution, and support should match the specifications of the large signage standard. Information will be displayed in Arabic and English.	Pcs	1	--	--
<b>4</b>	<b>System Training</b>				
4.1	Providing training on system operations and maintenance, as outlined in project requirements.	LS	~	--	--
<b>5</b>	<b>Health and safety</b>				
5.1	Supplying Personal Protective Equipment (PPE) and other health and safety equipment that meet all safety standards for all working personnel.	LS	~	--	--
<b>TOTAL (USD)</b>					<b>--</b>