



FUNDED BY THE EUROPEAN UNION
بتمويل من الاتحاد الأوروبي



RESPONSE TO REQUEST FOR QUOTES (SAMPLE TO BE FILLED, PRINTED, AND SIGNED)
INSTALLATION SOLAR ENERGY SYSTEM BOQ- Saida
February 24, 2023

SUPPLIER NAME/معلومات المزود: (To be filled)		RETURN QUOTATION TO: DPNA	
Contact Name/الاسم:		Contact Name/الاسم:	Mohamad Kozbar
Email/البريد الإلكتروني:		Email/البريد الإلكتروني:	procurement@dpna-lb.org
Phone/الهاتف:		Phone/الهاتف:	9617727004
Fax/الفاكس:		Fax/الفاكس:	9617727004
Mobile/موبايل:		Mobile/موبايل:	N/A
Address/العنوان:		Address/العنوان:	Corniche El Bahri, Hassib Abdel Jawad Street, Azzam Bldg., 3 rd floor, Saida, Lebanon
Date:التاريخ:			

INSTALLATION SOLAR ENERGY SYSTEM BOQ-Saida					
Item #	Description	Unit	Quantity	Unit Price	Total
1.0	Panel 545 Watt 49.5 Volt	Piece	18	\$	-
2.0	Inverter 10kw	Piece	1	\$	-
3.0	Lithium battery 8.7 kw ,48V	Piece	2	\$	-
4.0	Steel Structure Beams (4cm*8cm)+ (4cm*4cm), 2mm Thick , Galvanized. Works includes welding and all necessary accessories needed for fixation and any other application or materials needed to properly complete the works to the engineer's approval.	Piece	18	\$	-
5.0	All works needed for the installation of the system (Panel Board, Battery, Inverter, Cables,)	L.S	1	\$	-
6.0	Cables (2*6mm ² + 4*10mm ² + 35mm ²)	L.m	50	\$	-
7.0	Accessories (Concrete blocks,DC Cable ,AC Cable, Surge Arrestor,Cable Tray,Electric Box,Breaker (AC,DC),Cashcable,Original Z Clamps,Original U Clamps, Tribolt,Selfdrill Screws,Tie Wrap,Outdoor Flexible Tube , Fuse+Base,MC4 Connectors, Fixture,Lugs)	L.S	1	\$	-
8.0	Concrete Blocks	Piece	15	\$	-
9.0	Earth System(copper cable + piquets)	L.S	1	\$	-
	Total			\$	-