

#	Holding Tank Installation for Existing Pits	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
1	Desludging of existing Pit Works shall include but not limited to: - Removal of accumulated sludge via vacuum truck - Transport and discharge the desludged sewage into an approved Wastewater treatment plant	M3	48		\$ -
2	Supply and install a horizontal plastic septic tank with a capacity of 1000 liter 3 layers. Works shall include but not limited to: - Excavation of underground hole to fit the supplied tank - Supply and install a 4" opening for desludging purposes through the concrete base. - The tank should be put on a plane surface (ex.bedding) - Excavated material should be used to backfill the desludged pit - Excess excavated soil and debris should be deported to approved dump location	Unit	48		\$ -
3	Supply and cast reinforced concrete base (1.5*1.5m * 0.2m) with steel mesh 10mm, steel mesh, 1 bar every 25 cm	Unit	48		\$ -
4	Connecting the existing latrine outlet with the new installed holding tank. Works shall include but not limited to: - supply and install 4" PVC connection pipe between the latrine and the holding tank - Supply and install PVC fittings (reducers, elbows, P-traps and any needed accessory) -Supply and install squat seat	Unit	48		\$ -
				TOTAL	\$ -
				VAT 11% (if applicable)	\$ -
				Total After Tax	\$ -