

Item No	Contract Rate per unit	Unit	Qty.	Item Description	Amount USD
<b>1.00</b>				<b>GENERAL WORKS</b>	
101		l.s.	1.00	Mobilization and Demobilization	
<b>2.00</b>				<b>SEWER SYSTEM</b>	
201		l.m.	300.00	Supply of upvc SN4 400mmØ Pipe & Fittings	
202		l.m.	300.00	Trench Excavation - Type T2.H3 (5-7 m)	
203		m3	2,750.00	Pumping out water from the trench (Dewatering)	
204		l.m.	300.00	Supply and install proper sheet piles on all sides of the excavation to support the trench and to protect the railway and the electricity pylons	
205		l.m.	300.00	Sand Bedding and Surround, 400mmØ	
206		l.m.	50.00	RC Bedding & Surround, 400mmØ	
207		l.m.	300.00	Pipe laying of Upvc SN4, 400mmØ	
208		l.m.	300.00	Backfilling of Trenches - Type T2.H3	
209		units	10.00	Construction of Manholes - M2H3/C2H3	
210		units	10.00	Manhole Cover with A Frame, Grade A	
211		l.m.	300.00	Testing and Commissioning of Sewer Line	
212		units	10.00	Testing and commisioning of Manholes	