

Date:



Intervention Title BOQ

(P-code Name)

Item #	Activity Description	Unit	Quantity	Unit Price	Total
Construction of latrine		1			
1	Concrete base for latrine floor (140cm x 140cm x 20cm)	piece	1		
2	WC suite (Squat WC)	piece	1		
3	Superstructure (4cm x 4cm)	meter	28		
4	Zinco sheet	m ²	10		
5	Metallic wire mesh	m ²	2		
6	Bolts 10cm	piece	4		
7	Bolts 3cm	piece	50		
8	Door Lock	piece	2		
9	Zinco Coating (dutchboy)	kg	1		
10	Zinco Paint (dutchboy)	kg	1		
11	2000L Horizontal Striped Poly-Tank 3 Layers (for septic tank or holding tank)	piece	1		
12	Excavating by machine to reduce levels	m ³	4		
13	4 in. PVC Pipe	meter	2		
14	4 in. PVC 45°/90° Elbow	piece	1		
15	4 in. PVC Sewer and Drain Tee	piece	3		
16	4 in. PVC Cleanout Plug (سدة حكش)	piece	3		
17	4 in. PVC drain pipe fittings U-shaped airtight water Trap	piece	1		
18	A plate with DPNA and UNICEF logo 30*20 cm should be fixed to the superstructure in a visible way, the design of the plate should be approved by the engineer	piece	1		
Construction of latrine for disabilities & elderly people		1			
1	Concrete base for latrine floor (240cm x 240cm x 20cm)	piece	1		

2	Concrete pathway (300cm x 100cm x 20cm)	piece	1		
3	WC suite (Toilet Seat)	piece	1		
4	Parallel Steel Bars	meter	3		
5	Superstructure (4cm x 4cm)	meter	28		
6	Zinco sheet	m ²	10		
7	Metallic wire mesh	m ²	2		
8	Bolts 10cm	piece	4		
9	Bolts 3cm	piece	50		
10	Door Lock	piece	2		
11	Zinco Coating (dutchboy)	kg	1		
12	Zinco Paint (dutchboy)	kg	1		
13	2000L Horizontal Striped Poly-Tank 3 Layers (for septic tank or holding tank)	piece	1		
14	Excavating by machine to reduce levels	m ³	4		
15	4 in. PVC Pipe	meter	2		
16	4 in. PVC 45°/90° Elbow	piece	1		
17	4 in. PVC Sewer and Drain Tee	piece	3		
18	4 in. PVC Cleanout Plug (سدة حكش)	piece	3		
19	4 in. PVC drain pipe fittings U-shaped airtight water Trap	piece	1		
20	A plate with DPNA and UNICEF logo 30*20 cm should be fixed to the superstructure in a visible way, the design of the plate should be approved by the engineer	piece	1		
Rehabilitation of Latrine and/or Holding Tank			1		
1	Rehabilitating the Latrine through: - Door fixation - Corrosion repair - Concrete cracking repair - Painting works - Plumbeing works	Lumpsum	1		
2	Provide, install and connect a plastic holding tank with a capacity of 2000 litter 3 layers with a 4" opening for desludging purposes. Work includes all needed excavation installation and materials.	piece	1		

3	A plate with DPNA and UNICEF logo 30*20 cm should be fixed to the superstructure in a visible way, the design of the plate should be approved by the engineer	piece	1		
Desludging		1			
1	Removing sediments through vacuum truck Unit price per m3 of wastewater for desludging and internal transport from the holding tank/septic tank to the wastewater treatment plant (location of existing wastewater treatment plant in Zawtar)	m ³	1		
1000L Water Tank		1			
1	1000L Cylindrical Poly-Tank	piece	1		
2	Steel Stand for water tank 6cm x 6cm (150cm x 125cm x125cm)	piece	1		
300L Water Tank		1			
1	300L Cylindrical Poly-Tank	piece	1		
Construction of septic tank system		1			
1	4000L Horizontal Striped Poly-Tank 3 Layers	piece	1		
2	3000L Horizontal Striped Poly-Tank 3 Layers	piece	1		
3	2000L Horizontal Striped Poly-Tank 3 Layers	piece	1		
4	1000L Horizontal Striped Poly-Tank 3 Layers	piece	1		
5	500L Horizontal Striped Poly-Tank 3 Layers	piece	1		
6	300L Horizontal Striped Poly-Tank 3 Layers	piece	1		
7	Excavating by machine to reduce levels	m ³	1		
8	Backfilling with Gravel, Sand and Base Coarse for the filtration trench	m ³	1		
9	4 in. PVC Pipe	meter	1		
10	4 in. PVC 45°/90° Elbow	piece	1		
11	4 in. PVC Sewer and Drain Tee	piece	1		
12	4 in. PVC Cleanout Plug (سدة حكش)	piece	1		
Additional Pipes and Fittings		1			

1	2 in. PVC Pipe	meter	1	
2	4 in. PVC Pipe	meter	1	
3	6 in. PVC Pipe	meter	1	
4	8 in. PVC Pipe	meter	1	
5	2 in. PVC Connection	piece	1	
6	4 in. PVC Connection	piece	1	
7	6 in. PVC Connection	piece	1	
8	8 in. PVC Connection	piece	1	
9	2/4 in. PVC Convertor	piece	1	
10	4/6 in. PVC Convertor	piece	1	
11	6/8 in. PVC Convertor	piece	1	
12	2 in. PVC 45°/90° Elbow	piece	1	
13	4 in. PVC 45°/90° Elbow	piece	1	
14	6 in. PVC 45°/90° Elbow	piece	1	
15	8 in. PVC 45°/90° Elbow	piece	1	
16	2 in. PVC Sewer and Drain Tee	piece	1	
17	4 in. PVC Sewer and Drain Tee	piece	1	
18	6 in. PVC Sewer and Drain Tee	piece	1	
19	8 in. PVC Sewer and Drain Tee	piece	1	
20	2 in. PVC Cleanout Plug (سدة حكش)	piece	1	
21	4 in. PVC Cleanout Plug (سدة حكش)	piece	1	
22	6 in. PVC Cleanout Plug (سدة حكش)	piece	1	
23	8 in. PVC Cleanout Plug (سدة حكش)	piece	1	
24	4 in. PVC drain pipe fittings U-shaped airtight water Trap	piece	1	
25	Bathroom manhole construction	piece	1	
26	Street Manhole construction	piece	1	
27	Floor drainage	piece	1	
Site Restoration			1	
1	Rehabilitating the site to return to it's original state or improving the site through concrete leveling	m ³	1	
Total Cost				\$ -