BI	BILL OF QUANTITIES-MARITIME ACADEMY-MECHANICAL PARKING WORKSHOP					
ITEM	DESCRIPTION	Unit	Qty.	Unit Price	Total Price	
Ι	Civil Division					
1 1.1	Demolition works Demolition of concrete wall (h=1.5m, w=3m), including	LS	1			
2	debris discharge and pickup transportation Concrete and masonry works					
2.1	Construction of masonry wall 20 cm thick (Height around 3 m).Including supply and transportation of materials: masonry blocks, black cement, sand, gravel, steel rods, wood for concrete molding	SQM	63			
2.2	Construction of masonry wall 12 cm thick (Height around 3 m). Including supply and transportation of materials: masonry blocks, black cement, sand, gravel, steel rods, wood for concrete molding	SQM	90			
2.3	Pouring and molding concrete lintels and jambs around doors. Including supply and transportation of materials: masonry blocks, black cement, sand, gravel, steel rods, wood for concrete molding	LM	17			
2.4	Install Extruded polystyrene sheets (2cm-blue) for insulation between the double masonry walls. Including supply and transportation of the sheets.	SQM	90			
2.5	Install Acoustic Extruded polystyrene sheets (5cm-yellow) with geotextile on the floor, with 10 cm baton and 8mm steel. Including a concrete ramp on the entrance of the workshop. Including supply and transportation of materials: sheets, black cement, sand, gravel, steel rods, wood for concrete molding	SQM	115			
2.6	Plaster works: Apply plaster to all masonry walls (labor and material)	SQM	270			
3	Carpentry					
3.1	Supply and installation of new painted Steel door with acoustic insulation, with hardware (handle, lock, hinges). Oven painted. Dimensions: 2.4 m width x 2.4 m height. (labor and material)	LS	1			
3.2	Supply and installation of new painted Steel door with hardware (handle, lock, hinges). Oven painted. Dimensions: 0.90 m width x 2.2 m height. (Labor and	LS	1			
3.3	Supply and install white sliding plastic doors for the bathrooms with hardware (handle, lock, hinges) dimensions: 0.75 m width x 2.2 height	LS	2			
4	Aluminum Supply and install black aluminum window, double glazed tempered glass Sidem 2000 profile, dimensions (w=3m,					
4.1	h=1.5). 1 side of the window with aluminum louvre (0.75, 0.75). Supply and install outdoor aluminum safety fence in front of the window (w=3m, h=1.5)	LS	1			
4.2	Supply and install black aluminum cover for the AC outdoor split units	LS	4			
5	Painting works Walls paints: Supply and apply two coats of oil base paint on					
5.1	internal walls, including surface preparation, sanding, and precise putty touch-ups. Color selection to be determined. Scaffolding included. (Labor and material)	SQM	300			

ITEM	DESCRIPTION	Unit	Qty.	Unit Price	Total Price
52	Ceiling paint: Supply and apply two coats of oil base paint on internal ceiling, including surface preparation, sanding, and precise putty touch-ups. Color selection to be determined. Scaffolding included. (Labor and material)	SQM	100		
5.3	Concrete floor epoxy painting, including concrete sanding and floor preparation, application of Grout when needed. (labor and material)	SQM	100		

BI	BILL OF QUANTITIES-MARITIME ACADEMY-MECHANICAL PARKING WORKSHOP					
ITEM	DESCRIPTION	Unit	Qty.	Unit Price	Total Price	
6.2	<u>Miscellaneous</u> Debris discharge and pickup transportation Including workers and transportation from underground Supply of protection materials for floors (carboard, nylon, tape) and debris bags Insurance (Contractor's All Risk)	LS LS LS	1 1 1			
	To Collection \$					

BILL OF QUANTITIES-MARITIME ACADEMY-MECHANICAL PARKING WORKSHOP						
ITEM	DESCRIPTION	Unit	Qty.	Unit Price	Total Price	
	Total from page 1 & 2 Total from page 3				\$ - \$ -	
	Total Before Tax	\$			-	
	VAT	\$			-	
	Total TTC	\$			-	