

**Minifoot rehabilitation - Roum**  
**REQUEST FOR QUOTATION: No. RFQ/CDCS-RM001**

**BOQ**

Item #	Description	Unit	Quantity	Unit Price	Total
1.1	Preparing floor: dimensions 30m *17m Cut arround the existing concrete floor (perimeter) and remove blackfill (depth 17cm)	m2	510		\$ -
1.2	Supply base coat + roller flooring to unify the ground level (compacting to 5 cm)	m2	510		\$ -
1.3	Insert rubber joint all around the the perimeter of the new slab (preventing cracks)	Lm	94		
1.4	Supply and apply steel grid creating squares maximum 18cm using Ø 10 mm2 torcadé and raised at least 2cm from base coat level. Apply cement with thikness 12cm with upper layer ready to be painted	m2	510		\$ -
	<b>Total</b>				\$ -