

Project Name: SHABAKE 2		
DESCRIPTIONS	Unit	Quantity
1- Al Boustan Restaurant located in Qaa El Rim		Quantity
Carefully demolish floor tiles for Bathroom Supply and install 300*300 Ceramic floor tiles for Bathrrom , bedded and jointed in cement and sand mortar, including grouting	m2	60
Supply and install 2 aluminum doors (toilet) 2*1	U	2
Supply and install Sanitary Fixtures for toilet, price to include: Drainage pipes Under tiles and embedded in walls. Cold water under tiles and embedded in walls from drop of main pipes to the fixtures . Gate Valves All necessary and required accessories and fittings , hangers and supports , with all specified components.	LS	1
Supply and installation of European WC & Exposed Flush Tank including: [a] valve (copper), [b] WC cistern (porcelain), [c] cistern cover (porcelain), [d] seat cover (plastic), [e] complete flushing system (copper) , [f] water connection (1/2" PPR, hidden) & sewer connection (4" PVC, hidden), [g] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1
Supply and installation of normal size ceramic wash basin ~(50x40cms) including: [a] frame, [b] outlet (copper/chrome), [c] water connection (1/2" PPR, hidden) & sewer connection (2" PVC, hidden), [d] trap (plastic), [e] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1
Supply and install Floor Drain (15x15 cm, stainless)	U	2
Supply, Install, connect , test , and commission the lighting fixtures: Type Ceiling surface mounted lighting fixture, with " Globe "led Light for WC	LS	6

Supply and Install PVC Ceiling for Toilet, PVC sdimension: 3m*7m	m2	21
Supply and Install PVC Ceiling for kitchen, PVC sheets to be installed on 4*4cm wood beams. Kitchen dimension: 2.7m*6.3m	m2	17
Supply and Install Resin sink for kitchen, work includes installation of Kitchen cupboard, along with the needed supports L=1 m, W=0.6 m	U	1
Supply and install of water mixer for kitchen sink including: [a] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1
Supply and Install Metal shelves 2*0.60*40	U	1
Supply and Install SS food graded aluminum table for work 1*1	U	1
Supply and install toilet fan exhaust (standard) with all necesseray wiring	U	2
Welding and painting of the existing metal stair L=6m, W=2m.	U	1

2- For Al Raii Chtoura located in Qaa El Rim	Unit	Quantity
Supply and Instal PVC sliding door 2.1m*4m Specifications: Lubron, Color (white)	U	1

3- Beit El Mouneh located in Hawsh al Oumara	Unit	Quantity
Supply and Install PVC Ceiling for kitchen, PVC sheets to be installed on 4*4cm wood beams. Kitchen dimension: 6m*6.4m	m2	1
Suppluy Adjustable stools (chairs) - stools adjustable in height so it can be used by kids and adults	U	12
Suuply Middle Table , Specifications: 180cm x 120cm ,Adjustable height Low 40 cm, High 80 cm ,Stainless steel	U	1
Supply and install new aluminium kitchen cabinat above the kitchen sink L=2 m, W= 0.35 m, H=0.55 m	U	1

4- Cave Abou Hanna located in Karak Nouh	Unit	Quantity
Supply and install Wood Ceiling 9*4m (Pine Wood), wood panels (Pine) supporting the ceiling to be executed with the same specifications as the existing ones.	m2	36
Supply, Install, connect , test , and commission the lighting fixtures: Type Ceiling surface mounted lighting fixture, with " SPOT" Lights. Wires to be properly connected using PVC tubes and electric boxes. Spacing of the lights will be decided during the installation process	U	36
Supply and install wooden door with frame. Approximate size: width=132cm, height=220cm, frame thickness 4 cm , complete with paint, frame, architrave and CE approved ironmongery (atleast hinges, lock with key, and handle) including labours	U	1
Supply and install Sweden wood tasting bar (Rounded, L: 2.25m, H=1.2). Work includes proper installation of the wood, fixing using bolts, scrubing and painting all element (Bar Top and vertical panels).	U	1
Supply & install of Aluminum Window for Rooms (L:1.75m, H: 1.32m). Works include all necessary accessories with Insect Screen in accordance with the following details: - Aluminum Profile - Standard Profile Colors (White) - Accessories - Double Glazed Design: Sliding window	U	2
Supply and install Tv Samsung 40 inch Smart : Display: 40 in, VA, Edge LED, 3840 x 2160 pixels Viewing angles (H/V): 178 ° / 178 ° Brightness: 400 cd/m ² Static contrast: 4400 : 1 Refresh rate: 50 Hz / 60 Hz Frame interpolation: 120 MR (Motion Rate) TV tuner: Analog (NTSC/PAL/SECAM), Clear QAM, ATSC Cores: 4 Dimensions: 914.4 x 530.9 x 58.4 mm	U	1

<p>High Bar Chairs - Tested for: 243 lb - Sizes in inch</p> <p>Width: 15 3/4 "</p> <p>Depth: 17 3/4 "</p> <p>Height: 35 7/8 "</p> <p>Seat width: 15 3/4 "</p> <p>Seat depth: 13 3/4 "</p> <p>Seat height: 24 3/4 "</p>	<p>U</p>	<p>12</p>
<p>Wood Barrels</p>	<p>U</p>	<p>4</p>

5- COOP Wadi Al Arayesh Production located in Wadi Al Arayesh	Unit	Quantity
Supply and install Prefab house 4*4m without cement base. The Prefab house is made of (1 entrance door, 2 aluminum windows, 1 toilet, 1 PVC toilet door and 1 kitchen)	U	1
Provide and Install stainless steel kitchen sink, overall dimensions 100 x 60 cm, fixed using steel angled supports scaffolding, including provide and install waste fitting heavy duty pipe Easy flex plug, with all accessories including accessories, material, labor, PVC adhesive, Silicone and needed tools.	U	1
Provide & install water heater (GAZ) capacity of 40 liters, including fixtures, fittings, piping and all accessories. National quality approved by the Engineer in charge	U	1
Supply and installation of European WC & Exposed Flush Tank including: [a] valve (copper), [b] WC cistern (porcelain), [c] cistern cover (porcelain), [d] seat cover (plastic), [e] complete flushing system (copper, Itany brand) , [f] water connection (1/2" PPR, hidden) & sewer connection (4" PVC, hidden), [g] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1
Supply and installation of normal size ceramic wash basin ~(50x40cms) including: [a] frame, [b] outlet (copper/chrome), [c] water connection (1/2" PPR, hidden) & sewer connection (2" PVC, hidden), [d] trap (plastic), [e] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1
Contractor to perform complete electrical and mechanical connection to the existing networks	LS	1

6- Domaine Ste. Anne located in Rayak	Unit	Quantity
Repair, fix and clean wooden doors of any size and kind. Works include cutting, installing new panels and boards (glue, nails and screws), putty and paint 2 coats. Provide all needed accessories (hinges, handles, locks, glass).	U	4
Repair, fix and clean wooden windows of any size and kind. Works include cutting, installing new panels (glue, nails and screws), putty and paint 2 coats. Provide all needed accessories (hinges, handles, locks, glass).	U	5
Supply and Install PVC Ceiling for kitchen, PVC sheets to be installed on 4*4cm wood beams. Dimension: Kitchen(3*2.5), Toilet (2.2*2.6), Room#1 (4*4), Room#2 (4*4)	m2	45
Carefully demolish existing kitchen sink and toilet. Debris to be moved to the dump site	LS	1
Supply and install Sanitary Fixtures for kitchen and toilet, price to include: Drainage pipes Under tiles and embedded in walls. Cold and hot water under tiles and embedded in walls from drop of main pipes to the fixtures . Gate Valves All necessary and required accessories and fittings , hangers and supports , with all specified components.	U	2
Provide and Install Stainless Steel kitchen sink, overall dimensions 120 x 60 cm, fixed on supports, provide and install waste fitting heavy duty pipe Easy flex plug, with all accessories including accessories, material, labor, PVC adhesive, Silicone and needed tools.	U	1
Supply, Install, connect , test , and commission the lighting fixtures for kitchen: Type Ceiling surface mounted lighting fixture, with " LED luminaire 60X60" Light for kitchen	U	2
Supply and installation of European WC & Exposed Flush Tank including: [a] valve (copper), [b] WC cistern (porcelain), [c] cistern cover (porcelain), [d] seat cover (plastic), [e] complete flushing system (copper, Itany brand) , [f] water connection (1/2" PPR, hidden) & sewer connection (4" PVC, hidden), [g] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1

Supply and installation of normal size ceramic wash basin ~(50x40cms) including: [a] frame, [b] outlet (copper/chrome), [c] water connection (1/2" PPR, hidden) & sewer connection (2" PVC, hidden), [d] trap (plastic), [e] all necessary materials, accessories, requirements and manpower to make it properly serviceable.	U	1
Supply and install 300*300 Ceramic floor tiles for Bathrrom , bedded and jointed in cement and sand mortar, including grouting for walls and floor	m2	27
Supply and install of lighting point for bathroom including supply of electrical PE conduits, power socket, boxes and cables, light switch, waterproof light point and installation of conduits, boxes	U	1
Supply and install Complete Electrical Network , including wires, boxes, tubes and connection to existing panel boards.	LS	1
Supply and install new Panel board 6 modules, withh all the needed cuircuit breakers	U	1
Flush mounted switch, installed connected and tested, including supplying of conduits, conduit accessories and supports, conductors, junction derivation , and outlet boxes. with the installation only of switches and all other accessories. Labor, tools, transport, testing for One gang, one way single pole switch	U	6
Apply priming coat and 2 coats of Emulsion paints (CE approved) for walls. All works have to be executed after surface preperation, it must be smooth, leveled and clean.Putty should be applied for the hole surface, then sandpapers must be used in order to make the surface ready for paint. Cover all electric, wash and wood accessories using roll of painter's tape.	m2	250
Apply priming coat Wooden Ceiling . All works have to be executed after surface preperation, it must be smooth, leveled and clean.	m2	40
Supply and repair wood ceiling	m2	10

<p>Flush mounted socket, installed connected and tested, including supplying of conduits, conduit accessories and supports, conductors, junction derivation, and outlet boxes. with the installation only of sockets, wall plate or cover and all other accessories.</p> <p>Labor, tools, transport, testing for wall socket outlet</p>	U	6
<p>Supply and Deliver Master bed - Material: Backrest: High-density + down back Skeleton/Frame: Solid wood Support Legs: Solid wood</p>	U	1
<p>Supply and Deliver Single bed - Material: Backrest: High-density + down back Skeleton/Frame: Solid wood Support Legs: Solid wood</p>	U	1
<p>Supply and deliver Mattresses ,covers . Pillows: 1 for signle bed and one for Master bed (color white)</p>	U	1