

#	Items description		Quantity	Unit	Unit cost (LBP)	Total cost (LBP)	Specifications
	Steel Works	اعمال الحديد					
1	Wall Support	حمالة	275	item	-	-	The wall support is 1 meter long and made up of 4 shelves, each shelf is 50 cm long, covered with a plastic pipe of diameter 50 mm pvc, a wood must be cut and installed also in it for isolation as shown in the figure 2 in blue .The wall support must be painted ameron.
2	Cable Ladder	سلم حديد معزول للكابلات	1	item	-	-	A cable ladder is to be installed next to the control room or above it as shown in figure 3, it is also isolated by a 50mm pvc pipe
3	Door for the control room	باب حديد لغرفة التحكم	1	item	-	-	A door made up of for shelves for the control room contains ventilation openings and each shelf is 200cm * 50cm

